



T02	03.04.19	OJR	TXK	NIS	ACD ADDED AND CCTV REMOVED
T01	07.03.19	EIL	TXK	NIS	TENDER ISSUE

Rev	Date	By	Chk	Aprvd	Description
-----	------	----	-----	-------	-------------

PROJECT
Tavistock Guildhall

CLIENT
Tavistock Guildhall



www.methodllp.com Swindon Tel: 01793 822044

DRAWING TITLE
Proposed Security, Access Control & Fire Alarm Services First Floor

SUITABILITY
D2 - FOR TENDER

DATE	SCALE	DRWN BY	CHK BY	APVD BY
08.01.19	1:50 - A1	BMAP	TXK	NIS

DRAWING NUMBER	REVISION NO.
716LGH-MET-00-01-DR-E-Ss_75-0001	D2- T02

Scaling Note: Do NOT scale from this drawing.

- Legend:**
- COURT ROOM CAMERA
 - ACCESSED CONTROLLED DOOR
 - INTRUDER ALARM KEYPAD LINKED BACK TO MAIN INTRUDER ALARM PANEL IN GATEWAY RECEPTION
 - AUDIO VISUAL INTERCOM AND DOOR RELEASE
 - SALTO ACCESS CONTROLLED DOOR
 - REED SWITCH
 - REFUGE INTERCOM
 - ACCESSED CONTROLLED LIFT
 - INTRUDER ALARM ZONE FOR TOWN COUNCIL
 - INTRUDER ALARM ZONE FOR SHARED
 - RED BREAK GLASS
 - PUSH TO EXIT BUTTON
 - DUELLED PIR/MOTION DETECTOR

- Notes:**
1. DO NOT SCALE THIS DRAWING. ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE STATED.
 2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S STRUCTURAL ENGINEERS AND M&E DRAWINGS AND THE M&E SPECIFICATION, SAMPLES SHEET AND ROOM DATA SHEETS.
 3. ALL ITEMS OF EQUIPMENT SHALL BE INSTALLED AS TO THE MANUFACTURER'S RECOMMENDATIONS.
 4. ALL INFORMATION AND LAYOUTS DETAILED ON THIS DRAWING ARE SUBJECT TO SITE DIMENSION CHECKS.
 5. INTRUDER ALARM REED SWITCHES SHALL BE INSTALLED ON BOTH LEAVES OF ALL DOUBLE LEAF AND DOOR AND A HALF LEAF DOORS.
 6. ALL EQUIPMENT SHALL BE INSTALLED IN MAINTAINABLE LOCATIONS.
 7. ALL WIRING SHALL BE CONCEALED VIA CAST IN CONDUIT. THIS REQUIRES DETAILED COORDINATION WHICH SHALL BE UNDERTAKEN BY THE ELECTRICAL SUB-CONTRACTOR.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION	
FOR DETAILS OF SITE-WIDE AND GENERAL RISKS, TO BE READ IN CONJUNCTION WITH THESE NOTES. SEE THE CONTRACT DOCUMENTS AND, WHERE WORKS ARE NOTIFIABLE, THE PRE-CONSTRUCTION INFORMATION PACK ISSUED BY THE CDM CO-ORDINATOR	
IN ADDITION TO THE RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING RISKS AND INFORMATION:	
DISMANTLING / DEMOLITION (Future)	
Di:	
Dii:	
Diii:	
Div:	
IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT	